

NORTH CAROLINA Department of Transportation


STIP Project R-5799

(Pisgah Forest Intersection Improvements)

7/23/2024

Connecting people, products and places safely and efficiently with customer focus, accountability and environmental sensitivity to enhance the economy and vitality of North Carolina


Project Information



Purpose of the project:

- The area has experienced growth and development, Pisgah National Forest continues to attract growing numbers of visitors each year, leading to higher traffic volumes and increased congestion in the project area.

- Additionally, high levels of bicycle and pedestrian activity in the project area create a need for bicycle and pedestrian accommodations.




Intersection at Ecusta Road (SR 1512) to the bridge over the Davidson River

- 11'FT lanes with variable width concrete medians


- 10'Ft Mult-Use Path and 5'FT sidewalks

- Intersection stays signalized



Roundabout at US 276/NC 280/US 64


- Dual-Lane roundabout
- 11'FT Lanes with variable width concrete medians
- 10'FT Multi-use path
- 5'FT sidewalks




- Dual lane roundabout
- 11'FT lanes with variable median width

\$

- 10'FT Multi-use path



US 64 (Hendersonville Hwy) from proposed Roundabout to Davidson River Connector Road



- 11'FT lanes with 5'FT bike lanes
- 11'FT center turn lane
- 5'FT sidewalks





Construction

- Let : November 23rd, 2023
- Mountain Creek Contractors, Inc awarded project.
- Contractor began work in January 2024
- Work is anticipated to take three years to complete due to the phasing of the project.




Traffic Management Plan

-Y2- STA 11+99±


Phase I


Construction down US 64 (Hendersonville Hwy)



Phase II


Construction down Ecusta Road







Phase III


- Construct medians/curb/sidewalk/Multi-Use on US 64/NC 280





• Phase III going into IV







Phase IV


- Roundabout/s construction

- The only road that will be closed during construction is Deavor Road (SR 1511)



Phase IV continued...







Easy as pie

Questions?

Contact Us

Troy Wilson, PLS District Engineer tswilson@ncdot.gov 828-891-7911 **Tyler Rogers, PE Resident Engineer** rtrogersl@ncdot.gov 828-497-7333 Barry Mosteller Senior Project Manager bdmosteller@ncdot.gov 828-586-2141

🖵 ncdot.gov

X @NCDOT


G @NCDOT

O ncdotcom

in NCDOT

► NCDOTcommunications

•• NCDOTcommunications



View All Channels

Thank you!